



www.scgenterprises.com

Alternative Wastewater Systems

Archer Special Use District

Cheyenne, WY

Product Distribution

Product

Support

Installation / Start-up Date: March 2012

Project Summary:

Description: Effluent Sewer and AdvanTex[®] System

Design Flow: 15,000 GPD (Phase I)

Project Engineer: Western Research and Development

Installer: Integrated Water Services

Operator: Tom McDonough (County Facilities Operator)

Permitting Authority: WY Dept. of Health



Installation Assistance

Onsite Management Services

Maintenance Contracts

Effluent Sampling



System Summary:

Collection System:

 Small diameter effluent sewer with multiple Septic Tank Effluent Pumping (STEP) system connections.

Treatment System:

- 25,000-gallon Xerxes® recirculation tank
- Six AX100 AdvanTex[®] Filters
- 1,500-gallon precast concrete dosing tank
- Two Sanitron[™] UV disinfection lights
- Orenco® TCOM telemetry control panel

Dispersal System:

 Surface Discharge to lagoon for holding before re-use